KADUR DIVISION.

Abstract Notification.

The attention of the public is invited to the detailed notification dated the 16th May 1928, published on pages 487 and 488, Part VI of the *Mysore Gazette*, dated 24th May 1928, regarding the sales of Grass in the Plantations in the Kadur Division.

H. A. GOVINDA RAO,
District Forest Officer.

ENGINEERING DEPARTMENT.

TUMKUR DIVISION.

Abstract Notification.

Attention of the public is invited to the notification published in the *Mysore Gazette*, dated 24th May 1928, on page 493, Part VI, calling for the tenders for opening out a new road from Kolala to Yelekyathanahalli in the Tumkur Taluk.

The last date for presentation of the tenders is 15th June 1928.

V. V. PATANKAR,
Executive Engineer.

MYSORE DIVISION.

Notice dated 17th May 1928.

"Reference is invited to the advertisement published in detail in the *Mysore Gazette*, dated 24th May 1928 on pages 488 and 489 Part VI, advertising the last date.

L. A. H. WINCKLER,
Executive Engineer.

HASSAN DIVISION.

Notice dated 22nd May 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 22nd June 1928. An approximate estimate of quantities is given below. These quantinties are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate, conditions and specification may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed Tender for constructing a new tank near Gangoor, Belur Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a new tank near Gangoor in Belur Taluk, Hassan District.

No.	Items of work	Per	Quantity
	Bund		
1	Clearing jungle, etc.	Gr.	19
2	Clearing seat of bund and using to rear half	C.yd.	4,608
3	Cutting longing grips, etc.	Gr.	16
4	Excavating puddle trench	C.yd.	1,339
5	Do foundation to revetment	,,	2,276
6	Do core wall	,,	91
7	Benching rock	Lump	sum
8	Stone jelly concrete	C.ft.	968
9	Burnt stone in surki mortar—core wall	,,	3,208
10	Clay puddle wall	C.yd.	5,923
11	Earthwork to bund including watering and tamping with lead and lift.	,,	49,312
12	New stone revetment	,,	5,286
13	Gravel backing	,,	1,918
14	Turfing	S.yds.	8,028
15	Grade stones complete	Each	19
16	Index stones do	,,	19
17	Survey and constructive details stone	,,	1
18	Bench mark stone	,,	2
19	Gauge stone	,,	3
	Sluice No. 1.		
1	Earthwork excavation	C.yd.	90
2	Surki concrete	C.ft.	500
3	Burnt brick in surki mortar	,,	1,374
4	Burnt stone slabs 6" thick dressed	S.ft.	340
5	Surki mortar plastering	Sqr.	3·00
6	Cement plastering ½" thick	,,	1·23
7	Cement pointing	Lump	sum
8	Providing T. W. plug and rod with locking arrangement ..	Lump	sum
9	Cutting orifice, etc.	Lump	sum
	Sluice No. 2.		
1	Earthwork excavation	C.yd.	98
2	Surki concrete	C.ft.	643
3	Burnt brick in surki mortar	,,	1,516
4	Burnt stone slabs 6" thick dressed	S.ft.	430
5	Surki plastering	Sqr.	3·00
6	Cement plastering	,,	1·77
7	Cement pointing	Lump	sum
8	Providing T. W. plug rod, etc. complete	Lump	sum
9	Cutting orifice and etc.	Lump	sum
	Waste Weir.		
1	Earthwork excavation	C.yd.	3591
2	Surki concrete	C.ft.	975
3	Burnt brick in surki mortar	,,	2969
4	Burnt stone slabs 6" thick dressed	S.ft.	344
5	Surki plastering	Sqr.	2·00
6	Rough stone work	C.yd.	383
7	Turfing	Lump	sum
8	Providing clamps, etc.	Lump	sum
	Distribution.		
1	Excavating sluice channel	Lump	sum
2	Constructing relieving weirs...	R.ft.	140
3	Unforeseen works	Lump	sum

R. L. STEELE,
Executive Engineer.